

NH-ALSF TRACT 31-16  
Vandercook Oak & Aspen

Vilas County

Town 40 North, Range 7 East

Section 5 – W1/2SW1/4; SWNW

Section 6 – E1/2SE1/4; SENE

Section 7 – NE1/4; N1/2SE1/4; E1/2SW1/4; SENW

Section 8 – NWNW

Section 18 – N1/2NW1/4; SWNW

No bid bond required.

15% of the total sale bid value will be required as performance bond.

The cutting area is approximately 155 acres.

The contract period is 3 years.

All trees that will yield one or more 100-inch sticks to the minimum top diameter chosen by the bidder will be cut and utilized.

---

ESTIMATED VOLUME (TONS)  
MINIMUM TOP DIAMETER

<u>SPECIES</u>	<u>4"</u>	<u>Whole Tree</u>	<u>Advertised Price Per Unit</u>
Balsam Fir	95		\$ 6.60
Aspen	1440		\$ 12.10
Red Oak <sup>1</sup>	1955		\$ 23.40
Mixed Hardwood <sup>2</sup>	1495		\$ 14.30
<b>Total Minimum Bid Value</b>			<b>\$ 85,176.50</b>

---

<sup>1</sup>Volume includes 157 MBF of potential red oak logs.

<sup>2</sup>Volume includes 18 MBF of potential maple logs and 4 MBF of potential birch logs.

Volume consists of 50% red maple, 34% sugar maple, 15% white birch and 1% other. (Wt. conv. 2.39 tons/cord)

\*Note: Total sale volume equates to 32.16 tons/acre or 13.05 cords/acre.

Special Conditions:

1. Cutting must be concurrent for all species to be harvested. Tree length skidding is not allowed.
2. Biomass harvesting is not allowed. Do not cut, knock down, or utilize dead trees unless the tree poses a safety hazard during harvesting operations.
3. Slash within 50 feet of the Town road must be lopped and/or scattered to lie within two feet of the ground and pulled back at least ten feet behind the tree line concurrent with cutting.
4. Decking will be permitted along the snowmobile trails, as indicated on the map, in select areas only when an alternate decking site off the snowmobile trail is not possible. Snowmobile trail must be kept free of debris, snow covered in winter, and left in good condition for vehicle traffic at all times. All trails must be repaired to pre-harvest conditions before the start of each snow season. All landings and any new woods roads must be approved prior to sale start up.
5. If the contract is to be worked on during multiple time periods a mid-contract "pull-off" inspection meeting will be required. One-week notice shall be given by the contractor prior to moving equipment off-site. During the "pull-off" inspection, provisions needing attention will be documented. The contractor at that time can decide to remedy them before pulling equipment off or rectify them when moving back onto the site. If the latter is chosen, documented items shall be addressed before harvesting can continue.

**WISCONSIN  
DEPARTMENT OF NATURAL RESOURCES  
TIMBER SALE  
TRACT 31-16 VANDERCOOK OAK & ASPEN  
T40N R7E SECTIONS 5,6,7,8 & 18  
HARVEST ACRES - 155**



Scale: 4" = 1 Mile  
1:15,840

-  Aspen Regeneration Area (32 Acres): Cut all trees except red pine, white pine, spruce and red oak. Harvest all 1-5 inch aspen and maple concurrently.
-  Marked Oak Area (123 Acres): Cut all aspen, white birch, balsam fir and orange marked trees. Seasonal Restriction: Harvesting and skidding allowed from July 15 - April 15.


**Note: Do NOT cut trees marked with green paint or with an orange "X"**

The entire sale area lies within Area 5 - Big Arbor Vitae Loamy Hills Forest Production Area and Area 12 - Mixed Forest Native Community Area.

**Legend**

-  Section Corner
-  Red Line
-  Woods Roads
-  Snowmobile Trails
-  Highways and Town Roads
-  Sale #1101H - Marked Pine
-  Lakes

02,01  
11,12



11,12  
14,13

Trilby

01,06  
12,07

12,07  
13,18

Road

Vandercook

< 1.5 Miles to Hwy 51

< 2 Miles to Hwy M

06,05  
07,08